



# Memo

<b>To:</b>	EXECUTIVE DIRECTOR: PLANNING & ECONOMIC DEVELOPMENT <b>(ATTENTION: HAMISH LOUW)</b>
<b>From:</b>	MANAGER: INFRASTRUCTURE MANAGEMENT
<b>Enquiries:</b>	L. PIENAAR
<b>Collaborator number:</b>	
<b>Reference number:</b>	15/4/1 (328 & 329) P (750)
<b>Date:</b>	25 May 2021
<b>Subject:</b>	<b>APPLICATION FOR CONSOLIDATION OF ERVEN 328 &amp; 329 VAL DE VIE</b>

**Time Limit on Conditions:** These conditions will be limited to a period of 2 (two) years from the date as on the covering memo from this department. If after this period no construction has commenced ( this excludes any preparatory work or site clearance) all the studies carried out for the proposed development need to be updated and revised accordingly, this shall include compliance with the latest legislation, amended legislation, latest or amended standards and revised master planning.

**NOTE:** This comment covers a number of disciplines and each section needs to be dealt with by a competent specialist in that field co-ordinated by the consultant managing the application. No correspondence will be entered into with individual consultants

## INFORMATION REQUIRED/OUTSTANDING

Nil

## THE FOLLOWING CONDITIONS WILL APPLY

### 1 STREETS

1.1 No comment.

### 2 TRAFFIC

2.1 No comment.

### 3 STORMWATER

3.1 Provision must be made for an effective rainwater harvesting system to be planned and designed for all roof water. The volume of the storage facilities should be based on 0.02m<sup>3</sup>/m<sup>2</sup> roof area.

## **4 WATER**

- 4.1 The existing water meter and connection point must be accessible and unobstructed at all times;
- 4.2 Water saving devices shall be installed in toilets, bathrooms and basins;
- 4.3 Any existing system that is to remain shall be upgraded to minimum municipal standards.

## **5 WASTEWATER SERVICES**

- 5.1 All individual portions must be provided with a separate wastewater connection;
- 5.2 The existing wastewater connection to be retained system and ;
- 5.3 Any existing system that is to remain shall be upgraded to minimum municipal standards.

## **6 SOLID WASTE**

- 6.1 The Municipality undertakes to remove household refuse in accordance with its by-laws and shall make its own arrangements with the body corporate in the development for the removal of such household refuse;


## **7 DEVELOPMENT CHARGES**

- 7.1 Based on the information provided in the application, no Development Charges are payable by the developer.

## **8 GENERAL**

- 8.1 All of the works, including but not limited to; roads, stormwater, water, sewers, landscaping, irrigation, etc. shall be designed by a suitably registered (ECSA registration for the civil works and SACLAP registration for the landscaping) person and any such works shall be constructed under supervision of such registered person. All such design plans shall be submitted to the Civil Engineering Services Department of Drakenstein Municipality for approval prior to the commencement of construction;
- 8.2 All works where applicable shall be constructed to at least the minimum standards as set out in, Engineering Services: Municipal Standards;
- 8.3 The above conditions are to be complied with in stages.
  - 8.3.1 Requirements associated with the preparation of plans, drawings, permits, agreements and approvals, shall be complied with prior to construction;
  - 8.3.2 Requirements associated with the completion of construction, development charges, as-built drawings, maintenance management plans, agreements, etc. These will be complied with prior to the transfer of any property or occupation of any property/building in the phase; and

8.3.3 Proof of compliance for the requirements associated with long term operations must be available on request.



**LP PIENAAR (Pr. Eng)**  
**MANAGER: INFRASTRUCTURE MANAGEMENT**

I:\DEVELOPMENT APPLICATIONS\15 town planning\15-4-1\2021\comments\Erf 328, 329 - Val de Vie - Consolidation.docx  
LP/cb