



ANNEXURE D

Memo

To:	EXECUTIVE DIRECTOR: CORPORATE & PLANNING SERVICES (ATTENTION: C. VAN DER BANK)
From:	EXECUTIVE DIRECTOR: ENGINEERING SERVICES
Enquiries:	LH. SMITH
Collaborator number:	2299775
Reference number:	15/4/1 (11629, 11635 & 41612) P (2116)
Date:	19 March 2026
Subject:	PROPOSED REZONING, CONSOLIDATION AND PERMANENT LAND USE DEPARTURES – ERVEN 11629, 11635 & 41612, PAARL

These conditions will be subject to review by the Engineering Services Department upon receipt of Civil and/or building plans for approval. This may require all the studies carried out for the proposed development to be updated and revised accordingly, which shall include compliance with the latest legislation, amended legislation, latest or amended standards and revised master planning.

The aforementioned is based on the possibility of changes in the physical environment in respect of engineering infrastructure between date of issuing of conditions and actual building/construction being imminent, which may impact on available relevant infrastructure capacities as at time of initial issuing of conditions.

NOTE: This comment covers a number of disciplines and each section needs to be dealt with by a competent specialist in that field co-ordinated by the consultant managing the application. No correspondence will be entered into with individual consultants.

THE FOLLOWING CONDITIONS WILL APPLY

1 STREETS & TRAFFIC

- 1.1 Any new roads/streets and accesses will be the responsibility of the developer, including all internal and bulk connectors; and
- 1.2 Any alterations to the existing road network will be the responsibility of the developer which includes design, approval and construction of any additional traffic control and or traffic calming measures.

2 STORM WATER

- 2.1 Any new storm water networks will be the responsibility of the developer, including all internal and bulk connectors;
- 2.2 Only pre-development run-off of a 1:2 year storm event will be accepted into the existing system. Provision must be made to accommodate the detention of run-off for a 1:50 year storm event; and
- 2.3 Provision must be made for an effective rainwater harvesting system to be planned and designed for all roof water. The volume of the storage facilities should be based on 0.02m³/m² roof area.

3 WATER

- 3.1 Only one bulk water meter connection allowed and available at actual cost for the proposed development at the expense of the applicant/developer;
- 3.2 Water saving devices shall be installed in toilets, bathrooms and basins;
- 3.3 A water demand management plan must be submitted to the Civil Engineering Department and must include and indicate the measures to be put in place to conserve and manage water; and
- 3.4 Any existing system that is to remain shall be upgraded to minimum municipal standards.

4 WASTEWATER SERVICES

- 4.1 A 2m wide services servitude to be registered over the municipal midblock sewer system in favour of Drakenstein Municipality; and
- 4.2 Any existing system that is to remain shall be upgraded to minimum municipal standards.

5 SOLID WASTE

- 5.1 The Municipality undertakes to remove household refuse in accordance with its by-laws and shall make its own arrangements with the occupants of erven for the removal of such household refuse;
- 5.2 A waste recovery/recycling initiative has been implemented in Drakenstein and the development will have to be prepared to comply with any requirements as the project is rolled out; and
- 5.3 Such collection shall be from individual erven as a kerbside service.

6 DEVELOPMENT CHARGES

6.1 Based on the information provided in the application, the Development Charge payable by the developer is **R 18 246 (Excl. VAT)**. The levy is valid until **30 June 2026** where after a new calculation is required. The value has been calculated as follows:

6.1.1 Water = R 0

6.1.2 Sewer = R 0

6.1.3 Roads =R 0

6.1.4 Stormwater = R 0

6.1.5 Solid Waste = R 18 246

6.2 Note that the Development Charge calculated will only be applicable to the approved SDP provided in the application. If the developer wishes to increase the Gross Leasable Area of the development in future, resulting in an additional impact on engineering services, this department will investigate whether the developer is liable for the payment of Development Charges within the given legislative and policy frameworks.

7 GENERAL

7.1 ***Depending on the scale of expansion in future, additional Civil Engineering Specialist Reports may be requested by this department when the developer wishes to increase the GLA;***

7.2 ***When at any stage in future the municipality is required to take over ownership and maintenance of civil infrastructure, it will be the responsibility of the property owners to ensure all water and waste water connections adhere to municipal standards and by-laws;***

7.3 When any service is to be taken over by Drakenstein Municipality, any damage caused due to the construction of houses or any other construction activity shall be repaired by the Developer. Failure to do so will result in clearances and occupation certificates being withheld and remedial works shall be done by Drakenstein Municipality for the cost of the developer;

7.4 The developer is responsible for the payment of a Developers Charge (water, sewer, stormwater, solid waste and roads) which can be discounted against the bulk service cost needed for the development;

7.5 The developer is responsible for the funding of all connections to the bulk services and all internal works;

7.6 The findings of the bulk service capacity analysis carried out by councils consultant GLS Engineers, needs to be implemented simultaneously with the development;

- 7.7 All of the works, including but not limited to; roads, stormwater, water, sewers, landscaping, irrigation, etc. shall be designed by a suitably registered (ECSA registration for the civil works and SACLAP registration for the landscaping) person and any such works shall be constructed under supervision of such registered person. All such design plans shall be submitted to the Civil Engineering Services Department of Drakenstein Municipality for approval prior to the commencement of construction;
- 7.8 The whole of the works shall fall under the control of a single project manager;
- 7.9 The municipality shall be represented at all site meetings for the duration of the construction of the works and to this end timeous notification of such meetings shall be supplied to the Civil Engineering Services Department;
- 7.10 All works where applicable shall be constructed to at least the minimum standards as set out in, Engineering Services: Municipal Standards;
- 7.11 Where applicable all water network, (downstream of the valve immediately upstream of the bulk water meter, upstream of the connection to the existing system or intersection point with the existing road), sewer network, stormwater network and road network components shall be a private combined system and shall be indicated as such on all documents and plans;
- 7.12 All private combined systems (including but not limited to water, sewer, stormwater, roads, irrigation, etc.) shall be the joint and several responsibility (including but not limited to the administration of the joint account and operation and maintenance of the system) of the members of the homeowners association/body corporate and must be noted as such in any constitution of any such body and any such constitution must be submitted for approval by council. This constitution shall be notarially linked to each separate title deed;
- 7.13 A set of accurate as-built drawings as per Drakenstein Municipality: Civil Engineering Department's Standards must be submitted at the practical completion inspection; and
- 7.14 The above conditions are to be complied with in stages.
- 7.14.1 Requirements associated with the preparation of plans, drawings, permits, agreements and approvals, shall be complied with prior to construction;
- 7.14.2 Requirements associated with the completion of construction, development charges, as-built drawings, maintenance management plans, agreements, etc. These will be complied with prior to the transfer of any subdivided erf within the development property or occupation of any property/building in the phase; and

7.14.3 Proof of compliance for the requirements associated with long term operations must be available on request.




LH Smith

SENIOR MANAGER: INFRASTRUCTURE MANAGEMENT

I:\INFRASTRUCTURE MANAGEMENT\DEVELOPMENT APPLICATIONS\15 town planning\15-4-1\2026\Comments\Erven 11629, 11635 & 41612, Paarl - Rezoning, Consolidation & Departure.docx

LHS/sw

Date Payment Received:
Receipt Number:



Description of
proposed land use

Entire Consolidated Eff (Var)	#REF!				
0	0	0	0	0	0
#REF!					